

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

15-153-20182-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1974
06-18-1974
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.Operator's full Name: Empire Drilling Company.Complete Address: 650 Fourth National Bank Building, Wichita, Ks.Lease Name: Sis Well No. 3Location: 150' SW of CSE-SW Sec. 12 Twp. 1 Rge. (E)(W) 35County: Rawlins Total Depth 4245' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Sixbury was instructed to plug the well as follows:

284'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1775'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

N. L. Nichols

Conservation Division Agent