



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1973

8-21-73

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company, has this
date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Wilkinson Well No. 1

Location: 2200' FWL & 440' FSL-- Sec. 20 Twp. 1 Rge. (E)(W) 35

County: Rawlins Total Depth 4315' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

355'--8 5/8" Surface casing cement circulated with 225'.
Top of Dakota section @ 2125'.

Circulate hole with heavy mud. Pull DP to 2350' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 375' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

W. D. Nichols
Conservation Division Agent