

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1974
11-27-1974
CONSERVATION DIVISION
Wichita, Kansas

15-153-20145-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company,

Complete Address: P. O. Box #783, Great Bend, Kansas.

Lease Name: Chadderdon Well No. 1

Location: CSW-NE Sec. 11 Twp. 1 Rge. (E)(W) 35

County: Rawlins Total Depth 4394 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

252'--8 5/8" Surface casing, cement circulated.
4392'--5 1/2" Production casing cemented on bottom with 135 Sx. Well plugged back to 4362'. Top perforations from 4208' to 4215'.

Push plug to 4150', sand back to 4125' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 50 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent