



15-153-20704-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

FEB 1 1971

CONSERVATION DIVISION  
Wichita, Kansas

2-1-71

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Isern-Wells & George Reed,

Complete Address: Box #486, Ellinwood, Kansas.

Lease Name: Cahoj Well No. B-1

Location: 100' E of NE-SW Sec. 18 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4300' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 1875'.

Circulate hole with heavy mud. Pull DP to 2100' and displace 100 Sx.  
cement thru DP. Pull DP to 375' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*N. L. Nichols*  
Conservation Division Agent