



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

OCT 30 1963
 10-30-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co. has this

date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Bldg., Wichita, Ka.

Lease Name: Gaines Well No. 1

Location: CSW-SW Sec. 29 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4945 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

287'--8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 660' and 20 Sx cement.

"	"	280'	with $\frac{1}{2}$ sack hulls &
			20 Sacks cement.
"	"	40'	with $\frac{1}{2}$ sack hulls &
			10 sacks cement.

Very truly yours,

W. L. Nichols
 Conservation Division Agent