

4 060158

2-10

185

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-153-20,772-00-00
NW NW SE, SEC. 1, T 1 S, R 35 W/E

2200 feet from S section line
2200 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Wilkinson Well # 1

Operator: John O. Farmer Inc.

County Rawlins 137.47

Name & Address P.O. Box 352

Well Total Depth 4230 feet

Russell, KS

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address Wichita, KS

Company to plug at: Hour: 12:30PM Day: 10 Month: February Year: 19 91

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Inc. (phone) _____

were: Order 190 sxs. 60/40pos 6%gel 1/4# flocel per sx.

Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
02-21-1991
FFR 21 1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXX

Operations Completed: Hour: 12:30PM Day: 10 Month: February Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2930' with 25 sxs. Anhydrite 2910-2948'

2nd plug at 2170' with 100 sxs. Dakota at 1869-2169'

3rd plug at 320' with 40 sxs. Surface pipe to 269'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

Remarks: Halliburton Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXXXX did not) observe this plugging.

DATE 2-25-91

INV. NO. 30889

2-10

Handwritten initials

Signed [Signature]
(TECHNICIAN)
Herb Deines