

8-050116

7-9

297
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,777-00-00
C SE SW /4 SEC. 27, 01 S, 35 W
660 feet from S section line
3300 feet from E section line

Operator license# 5046 Lease CAHOJ A well # 1

Operator: RAYMOND OIL COMPANY INC. County RAWLINS

Address: P.O. BOX 48788 Well total depth 4440 feet
WICHITA, KANSAS 67201 Conductor Pipe: inch @ feet
(316)267-4214 Surface pipe 8 5/8 inch @ 302 feet

144.30

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: MURFIN DRILLING COMPANY License# 30606

Address: 250 N. WATER SUITE 300 WICHITA, KANSAS 67202

Company to plug at: Hour: PM Day: 9 Month: JULY Year: 1991

Plugging proposal received from: KEITH VANPELT

Company: MURFIN DRILLING COMPANY phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

- 1st plug @ 3090 feet with 25 sacks
- 2nd plug @ 2355 feet " 100 "
- 3rd plug @ 355 feet " 40 "
- 4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

Rat hole: 15 sacks

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 8:00 PM, Day: 9, Month: JULY, Year: 1991

Actual plugging report: Hole reported plugged as above.
Order 190 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

Remarks: Elevation: 3206, Anhydrite: 3071-3107 feet, Arbuckle: NONE.

Did NOT penetrate Arbuckle, cemented by HALLIBURTON SERVICES

I did[] / did not[X] observe the plugging. Marvin L. Miller

DATE 10-9-91

INV. NO. 33331

[Handwritten signature]

Marvin L. Miller P.I.R.T.II
(agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1991
10-8-91
CONSERVATION DIVISION
WICHITA, KS