

2

10-15

4-032267

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-153-20,811 - 68-00

SE NE /4 SEC. 05, 01, 36 W
3300 feet from S section line
660 feet from E section line

Operator license# 31730
Operator: Advantage Resources
Address: 1775 Sherman St. - #1375
Denver, CO 80203

Lease: Spears Well # 8-5
County: Rawlins 145,18
Well total depth 4467 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 224 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# _____

Address: Oakley, Kansas 67748

Company to plug at: Hour: P.M. Day: 15 Month: October Year: 1997

Plugging proposal received from: Bill Kalor

Company: Advantage Resources Phone: _____

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

11-03-1997
11:00 AM

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 12:30 A.M., Day: 15 Month: October, Year: 1997

Actual plugging report: 8 5/8" set at 224' w/165 sxs cwc. 5 1/2" set at 4431' w/400 sxs.
TOC 2100'. Prod. Perfs 4020' - 4124'. PBSD 4210'. Mixed and pumped down 5 1/2" 150 sxs
cement blend with 500# hulls mixed in backoff casing at 242'. Mixed and pumped down
5 1/2" - 100 sxs cement blend to circulate. Laid down 5 1/2" topped off 8 5/8" w/15 sxs
cement blend. Hole full of cement. Used total of 266 sxs cement blend and 500# hulls.
Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____; CASING _____ Elevation: _____ GL

INVOICED I did not observe the plugging.

Carl Goodrow
(agent)

DATE 11-4-97
INV. NO. 49419