

6 030418

15-153-30100-00-00

~~15-153-20692-00-00~~

PLUGGED

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

NE, SEC. 14, T. 1 S, R 35 (W) #

1980 feet from N/S section line

660 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Lease Name <sup>Savage</sup> ~~Chatterdown~~ Well # 1

Operator: Burch Exploration Inc.  
Name & Address: 6415 Nanette Way  
Colorado Springs, Colo.  
80907

County Rawlins 141.99

Well Total Depth 4369 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated Old Savage well (came with lease)

Plugging Contractor POE Well service License Number 6779

Address Oberlin Hill City Kansas

Company to plug at: Hour: AM Day: 17 Month: 4 Year: 19 85

Plugging proposal received from Mell Taylor

(company name) Burch Exp. Inc. (phone) \_\_\_\_\_

were: 8 5/8 @ 324 4 1/2 @ 4369 hole in 4 1/2 @ 2000' washed down sand to 2100' mudded up and drilled sand to 2500' couldn't drill anymore. Ordered 2000# 50/50 pg 6% gel 3% cc 50# gel 6% hulls. Halliburton Cement Co.

RECEIVED  
STATE CORPORATION COMMISSION  
04-20-1985  
APR 20 1985

Plugging Proposal Received by Carl Goodlow (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:AM Day: 17 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Pumped down 4 1/2 50# gel 6# hulls 180# Cem. mix. back side circulating Hooked on to back side and pumped 20# Cem. mix. Squeezed. May 200# Removed Halliburton tools cement stayed at surface Welder cut off casing to <sup>below</sup> plow depth Plugging Complete.

Remarks: (If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

DATE 5-6-85  
INV. NO. 7958

Signed Carl Goodlow (TECHNICIAN)

13  
4-26-85  
MJP