

6 030484

15-153-30097-00-00 D-10,255

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 2-26-63

CSWNW, SEC. 13, T. 1 S, R. 35 178

3300 feet from E & section line

4620 feet from S & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Lease Name Chattardon Well # 2

Operator: Burch Exploration Inc.

County Rawlins

Name & Address 6415 Nanchetta Way,

Well Total Depth 4500 feet

Colorado Springs Colorado

Conductor Pipe: Size _____ feet

80907

Surface Casing: Size 8 3/8 feet 288

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Poe Well Service License Number 6779

Address Oberlin Kansas

Company to plug at: Hour: PM Day: 23 Month: 4 YEAR: 85

Plugging proposal received from Mel Taylor JUN 24 1985

(company name) Burch Exploration (phone) _____

were: 8 3/8" set @ 288 w/ 225 af. 5 1/2" set @ 4499 w/ 300 af. Top Perf 4154

PBTD 4464 Order 200 af 5 1/2" sp gr 6 1/2" gel 3 1/2" cc. 3 af shells. 15 af gel.

sand. Halliburton Com. well water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12 PM Day: 23 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Spotted 2 3/8 tubing @ 3150 tagged filling, pumped
15 af Halliburton sand laydown tubing mix and spot 10 af cement
on top of sand laydown tubing Pump down 5 1/2 3 af shells
15 af gel. 170 af. Com. mix. Pump down backside w/
20 af Com. mix. Plug dropped 400' Halliburton filled with
100 af Com. mix. Squeezed 100th PST cement stayed at surface.

Remarks: Plug complete
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)