

6030484

15-153-30096-00-OR

API NUMBER ~~15-~~ 2-26-63

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CSWNW, SEC. 13, T. 1 S, R. 35 W/B

3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Lease Name Chattardas Well # 1

Operator: Burch Exploration Inc.
Name & Address: 6415 Nanchette Way,
Colorado Springs Colorado.
80907

County Rawlins 146.25

Well Total Depth 4500 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 288 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Poe Well Service License Number 6779

Address Oberlin Kansas

Company to plug at: Hour: PM Day: 23 Month: 4 Year: 19 85

Plugging proposal received from Mel Taylor

(company name) Burch Exploration (phone) _____

were: 8 5/8" act @ 288 w/ 225 af. 5 1/2" act @ 4499 w/ 300 af. Top Perf 4154
PBTD 4464 Order 200 af 50/50 pg 6 1/2 gal 3 1/2 cc. 3 af hulls. 15 af gel.
sand. Halliburton Cem. well-water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 PM Day: 23 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Spotted 2 3/8 tubing @ 3150 tagged fillup. Pumped
15 af Halliburton sand laydown tubing mix and spot 10 af cement
on top of sand laydown tubing Pump down 5 1/2 3 af hulls
15 af gel. 170 af. Cem. mix. Pump down backside of
20 af Cem. mix. Plug dropped 400' Halliburton filled with
100 af Cem. mix. Squeezed 100th PST cement stayed at surface

Remarks: Plug complete

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-26-85

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 8718

RECEIVED
STATE CORPORATION COMMISSION
06-24-1985
JUN 24 1985

CONSERVATION DIVISION
Wichita, Kansas