

9-9
4-062680

40R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,791-00-00

E2 SW SW /4 SEC. 01, 01 S, 35 W
660 feet from S section line
4950 feet from E section line

Operator license# 5135

Lease Sis well # 1

Operator: John O. Farmer, Inc.

County Rawlins

Address: 370 W. Wichita Avenue
Box 352
Russell, Kansas 67665

Well total depth 4330 feet ^{140.72}
Conductor Pipe: 8 5/8 inch @ 300 feet
Surface pipe 170 feet @ 283 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie R.T.D., Inc. License# 30684

Address: _____

Company to plug at: Hour: 1:45P.M. Day: 9 Month: August Year: 92

Plugging proposal received from: Bill Craid

Company: John O. Farmer, Inc. Phone: 913-483-3144

Were: Order 210 sks. 60/40 pozmix - 6% gel. - 3% cal. cl. - 1 sk. flocele and 8 5/8" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:45P.M., Day: 9, Month: September, Year: 92

Actual plugging report: _____

1st. plug @ 3037' w/25 sks.

2nd. plug @ 1700' w/25 sks.

3rd. plug @ 1100' w/100 sks.

4th. plug @ 300' w/25 sks.

5th. plug @ 40' w/10 sks.

15 sks. in Rathole.

10 sks. in Mousehole.

Remarks: Allied

Condition of casing(in hole): GOOD BAD Any plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2843 GL

I did[] / did not[X] observe the plugging.

DATE 10-2-92

INV. NO. 36306

RECEIVED
STATE CORPORATION COMMISSION
09-16-1992
SEP 16 1992

CONSERVATION DIVISION
WICHITA, KANSAS

Gilbert G. Scheck

(agent)

Form CP-2/3