

KANSAS

Form CP-3
Rev. 6-4-68

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20099-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1970
CONSERVATION DIVISION
Wichita, Kansas
12-1-70

Operator's Full Name Skelly Oil Company,

Complete Address 1860 Lincoln Street, Denver, Colorado.

Lease Name Frances H. Sabatka Well No. 3

Location CSW-NE Sec. 20 Twp. 1 Rge. (E) (W) 3

County Rawlins Total Depth 4371'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated.

Address 830 Sitton Place, Wichita, Kansas. License No.

Operation Completed: Hour 10:30 PM Day 26 Month 11 Year 1970

The above well was plugged as follows:

365'---8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2050' and displaced 100 Sx. cement thru
DP from 2050' to 1725'. Pulled DP to 390' and displaced 40 Sx. cement thru DP from
390' to 270'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 12/1/70

INV. NO. 2956-W