

KANSAS

af
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1972

CONSERVATION DIVISION
Wichita, Kansas

4-19-72

15-153-20136-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Rooney Well No. 1

Location NE NE NW
440' FNL & 440' FEL of NW/4 Sec. 25 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4410'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:00 PM Day 17 Month 4 Year 1972

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1950'.

Circulated hole with heavy mud. Pulled DP to 2175' and displaced 110 Cu. Ft. cement
thru DP from 2175' to 1850'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 4-19-72

INV. NO. 5587-42