

15-153-20162-00-00

Form CP-3
Rev. 6-4-68

KANSAS

W
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1973
8-21-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Wilkinson Well No. 1

Location SE SE SW 2200' FWL & 440' FSL of -- Sec. 20 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4315'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 4:30 AM Day 15 Month 8 Year 1973

The above well was plugged as follows:

355'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 2125'.

Circulated hole with heavy mud. Pulled DP to 2350' and displaced 110 Cu. Ft. cement
thru DP from 2350' to 2025'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/22/73
INV. NO. 7804-W

Signed: *W. L. D. [Signature]*
Well Plugging Supervisor