

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20145-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1974
11-27-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aspen Drilling Company,
Complete Address P. O. Box #783, Great Bend, Kansas.
Lease Name Chadderdon Well No. 1
Location CSW-NE Sec. 14 Twp. 1 Rge. (E) (W) 35
County Rawlins Total Depth 4394'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling,
Address Box #176, Chase, Kansas. License No. 683
Operation Completed: Hour 1:15 PM Day 22 Month 11 Year 1974

The above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated.
4392'--5 1/2" Production casing cemented on bottom with 135 Sx. Well plugged back to 4362'. Top perforations from 4208' to 4215'.
Pushed plug to 4150', sanded back to 4125' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 9 sacks gel following with 110 Cu. Ft. cement from 2075' to 1750' then 37 sacks gel from 1750' to 270' following with 30 Cu. Ft. cement from 270' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to base of cellar. Maximum pump-in pressure-300#. FSIP-150#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/2/74
INV. NO. 369-W