

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1971
CONSERVATION DIVISION
Wichita, Kansas
2-1-71

15-153-20104-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Isern-Wells and George Reed,
Complete Address Box #486, Ellinwood, Kansas.
Lease Name Cahoj Well No. B-1
Location 100' E of NE-SW Sec. 18 Twp. 1 Rge. (E) (W) 34
County Rawlins Total Depth 4300'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated _____
Plugging Contractor Gabbert-Jones, Incorporated,
Address 830 Sutton Place, Wichita, Kansas. License No. _____
Operation Completed: Hour 7:45 PM Day 28 Month 1 Year 1971

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pulled DP to 2100' and displaced 110 Sx. cement thru
DP from 2100' to 1745'. Pulled DP to 375' and displaced 30 Sx. cement thru DP from
375' to 285'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2-1-71

INV. NO. 3292-W