

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20123-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1971
CONSERVATION DIVISION
Wichita, Kansas
7-26-71

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Anselm Well No. 1

Location App: CNE-NW Sec. 18 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4320

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:30 PM Day 22 Month 7 Year 1971

The above well was plugged as follows:

284'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1925'.

Circulated hole with heavy mud. Pulled DP to 2150' and displaced 100 Sx. cement thru
DP from 2150' to 1825'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 7-29-71
INV. NO. 4064-W