

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
05-24-1971
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas

15-153-20116-00-00

Operator's Full Name George A. Reed,
Complete Address 1223 Union National Building, Wichita, Kansas.
Lease Name Cahoj Well No. A-1
Location CNW-SE Sec. 8 Twp. 1 Rge. (E) (W) 34
County Rawlins Total Depth 4280'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Rains & Williamson Oil Company, Incorporated,
Address 1425 Wichita Plaza Building, Wichita, Kans. License No. _____
Operation Completed: Hour 7:00 PM Day 22 Month 5 Year 1971

The above well was plugged as follows:

321'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1775'.

Circulated hole with heavy mud. Pulled DP to 2000' and displaced 100 Sx. cement thru
DP from 2000' to 1675'. Pulled DP to 330' and displaced 25 Sx. cement thru DP from
330' to 255'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 5-24-71
INV. NO. 3746-10