

KANSAS

Form CP-3
Rev. 6-4-68

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20135-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1972 *4-14-72*
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Skolout Well No. 1

Location NW-NW-NE Sec. 29 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:30 PM Day 9 Month 4 Year 1972

The above well was plugged as follows:

300'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 2025'.

Circulated hole with heavy mud. Pulled DP to 2350' and displaced 110 Cu. Ft. cement
thru DP from 2350' to 2025'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*
Well Plugging Supervisor

DATE 4/17/72
INV. NO. 5554-W