

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1972

CONSERVATION DIVISION
Wichita, Kansas

10-27-72

15-153-20141-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Micek Well No. 1

Location NW NW NW
110' FNL & 100' FWL of Sec. 28 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 3930'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 3:00 PM Day 25 Month 10 Year 1972

The above well was plugged as follows:

308'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 2025'.

Circulated hole with heavy mud. Pulled DP to 2300' and displaced 110 Cu. Ft. cement
thru DP from 2300' to 1975'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Dicks
Well Plugging Supervisor

DATE 10/27/72
INV. NO. 6539-W