

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20182-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
06-18-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,
Complete Address 650 Fourth National Bank Building, Wichita, Kansas.
Lease Name Sis Well No. 3
Location 150' SW of CSE-SW Sec. 12 Twp. 1 Rge. (E) (W) 35
County Rawlins Total Depth 4245'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas. License No.
Operation Completed: Hour 7:00 PM Day 11 Month 6 Year 1974

The above well was plugged as follows:

284'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1775'.

Circulated hole with heavy mud. Pulled DP to 2000' and displaced 110 Cu. Ft. cement
thru DP from 2000' to 1675'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor