

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20182-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1974
06-13-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drlg. Co.
Complete Address 650 4th Nat'l Bldg., Wichita, Kansas
Lease Name Sis Well No. 3
Location SE SW Sec. 12 Twp. 1 Rge. (E) (W) 35
County Rawlins Total Depth 4245'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Murfin Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 7 P Day 11 Month 6 Year 1974

The above well was plugged as follows:

RTD 4245' 8 5/8 csg set at 284' cwc 200 sk. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 2000' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 315' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 6/13/74
INV. NO. 9302-w