


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

RAWLINS County. Sec. 11 Twp. 1S Rge. 35 (~~XXXXX~~)(W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C NE SE  
Lease Owner Empire Drilling Company  
Lease Name Sis-Bennett Well No. 1  
Office Address 650 FOURTH NATIONAL BANK BLDG, WICHITA 2, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed DECEMBER 16 19 62  
Application for plugging filed DECEMBER 16 19 62  
Application for plugging approved DECEMBER 16 19 62  
Plugging commenced DECEMBER 16 19 62  
Plugging completed DECEMBER 16 19 62  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4340 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface - Shale & Sand	0	211	8 5/8"	202'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 540' with 20 sacks cement.  
Plug set at 200' with 20 sacks cement.  
Plug set at 35' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
12-27-1962  
DEC 27 1962  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 650 FOURTH NATIONAL BANK BLDG., WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
DAN J. KORNFELD (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Dan J. Kornfeld  
650 FOURTH NATIONAL BANK BLDG, WICHITA 2, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of December, 19 62

[Signature]  
Lucille H. Harr  
Notary Public.

My commission expires October 21, 1966



LOG

15-153-30093-00-00

COMPANY: Empire Drilling Company

CONTRACTOR: Empire Drilling Company

FARM: Sis-Bennett #1

LOCATION: C NE SE Section 11-1S-35W, Rawlins County, Kansas

COMMENCED: December 4, 1962

ELEVATION: 3140 KB

COMPLETED: December 16, 1962

POTENTIAL: D & A

\*\*\*\*\*

0	to	211	Surface - Shale & Sand
211	to	2089	Shale & Shells
2089	to	2300	Shale & Gyp
2300	to	2445	Shale & Gyp with pyrite
2445	to	2735	Shale & Gyp
2735	to	2865	Shale & Gyp with pyrite
2865	to	3003	Shale & Gyp
3003	to	3040	Anhydrite
3040	to	3260	Shale & Shells
3260	to	3970	Lime & Shale
3970	to	4000	Lime & Shale & Chert
4000	to	4025	Lime
4025	to	4130	Lime & Shale
4130	to	4140	Lime
4140	to	4190	Lime & Shale
4190	to	4315	Lime
4315	to	4340	Lime & Shale
4340			Rotary Total Depth

SET: 202' of 8 5/8" with 125 sacks.

SCHLUMBERGER ELECTRIC LOG TOPS:

Anhydrite	3013	+127
Admiral Group	3637	-497
Waubensee Group	3685	-545
Topeka	3845	-705
Deer Creek	3893	-753
Oread	3946	-806
Leavenworth	4019	-879
Douglas Sand	4036	-896
Lansing	4068	-928
Zone 2A	4125	-985
Zone 5	4173	-1033
Zone 6	4224	-1084
Zone 6A	4241	-1101
Zone 7	4267	-1127
Zone 8	4309	-1169
Base Kansas City	4338	-1198
Log Total Depth	4341	

STATE OF KANSAS  
DEC 27 1962  
CONSERVATION  
RAWLINS, KANSAS

\*\*\*\*\*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Sis-Bennett #1, C NE SE Section 11-1S-35W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

*Dan J. Kornfeld*  
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 21st day of December, 1962.

*Lucille H. Harr*  
Lucille H. Harr, Notary Public

My commission expires October 21, 1966.