

STATE OF KANSAS
STATE CORPORATION COMMISSION
200A Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,748 00-00

LEASE NAME Kletchka

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Frontier Oil Company

SEC. 29 TWP. 1S RGE. 35 (X) or (W)

ADDRESS 125 North Market, Suite 1720

COUNTY Rawlins

Wichita, KS 67202

PHONE#(316) 263-1201 OPERATORS LICENSE NO. 5140

Date Well Completed 4-10-90

Character of Well Oil

Plugging Commenced 8-31-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-31-95

The plugging proposal was approved on 8-31-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top _____ Bottom _____ T.D. 4490'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	385'	-0-
				4 1/2"	4465'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Set a drillable cast iron plug at 4150' & pumped 4 sx com. cem. on top of plug. Shot off 4 1/2" casing at 2347' & pumped 120 sx 60-40 poz cem, 10% gel & 200# hulls down 4 1/2" csg. Pulled 4 1/2" csg. to 290' from surface & pumped 85 sx 60-40 poz., 10% gel, down 4 1/2" csg. Cem. did circ. Pulled 4 1/2" csg. out of hole & loaded hole w/10 sx 60-40 poz cem., 10% gel. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service License No. _____

Address P. O. Box 426, Victoria, KS 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Frontier Oil Company

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jean Angle (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jean Angle

(Address) 125 North Market, Suite 1720
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of Sept., 19 95

JEAN HOLLAR
Notary Public - State of Kansas
My Appt. Expires May 5, 1998

Commission Expires: 5-5-98

Jean Hollar
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
SEP 07 1995
9-7-95