

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-20,811-00-00

LEASE NAME Spears

WELL NUMBER 8-5

1980 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 1 RGE. 36 (E) or (W)

COUNTY Rawlins

Date Well Completed 9-23-96

Plugging Commenced 10-15-97

Plugging Completed 10-15-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Advantage Resources, Inc.

ADDRESS 1775 Sherman St., Ste. 1900, Denver, CO 80203

PHONE# (303) 831-1912 OPERATORS LICENSE NO. 6926

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/15/97 (date)

by Mr. Carl Woodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No Logs sent earlier

Producing Formation Oread & Lansing KC Depth to Top 4019 Bottom 4125 T.D. 4470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Oread	Oil	4019	4030	8-5/8"	224	None
Lansing	Oil	4116	4122	4-1/2"	4431	243

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 150 sx of 60/40 pozmix + 10% gel & 500# of cottonseed hulls. Ran 5 bbls of water. Back tork casing off @ 243'. Pump 100 sx of 60/40 pozmix w/ 10% gel. Down 6 jts & pulled 243' of casing. Pushed rubber down 8-5/8" csg to 42'. Placed 15 sx cement on top of plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Well Service License No. 3152

Address P. O. Box 115, Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Advantage Resources, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Edward J. Ackman, President of Advantage Resources, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Edward J. Ackman, President
1775 Sherman St., Ste. 1900

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 97

[Signature]
 Notary Public

My Commission Expires: 9-9-98