

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-153-30100-00-00

WELL PLUGGING APPLICATION FORM

(File One Copy)

~~15-153-30100-00-00~~

API NUMBER March 1, 1962 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Burch Exploration Inc. OPERATORS LICENSE NO. 7448

ADDRESS 6415 Nannette Way, Colorado Springs, Colorado 80907 PHONE # (303) 598-2515

LEASE (FARM) Savage WELL NO. 1 WELL LOCATION C-NE-SE COUNTY Rawlins

SEC. 14 TWP. 1S RGE. 35W (E) or (W) TOTAL DEPTH 4371 PLUG BACK TD 4333

Check One:

DRILL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 324 CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2 SET AT 4367 CEMENTED WITH 200 SACKS

PERFORATED AT 4273 to 4275 4232 to 4234

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK X JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run 2 3/8 tubing with bit. Hole clean to

2750. Clean out sand to 2850. Call state plugger Carl Goodrow. Pump 50 sks. of gel and

6 sks. of hulls down casing. Mix 180 sks. of cement 6% gel and 3% C.C. Fill casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACCORDANCE WITH REGULATIONS OF THE STATE CORPORATION COMMISSION
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4-15-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND OTHER RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Melvin L. Taylor PHONE # (308) 345-3214 or 345-2422

ADDRESS 405 East 14th, Route 1, McCook, Nebraska 69001

PLUGGING CONTRACTOR Poe's Well Service LICENSE NO. 6779

ADDRESS P.O. Box 115, Oberlin, Kansas 67749 PHONE # (913) 475-3422

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: _____
(Operator or Agent)

DATE: April 25, 1985

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1985

CONSERVATION DIVISION
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1985

CONSERVATION DIVISION
WICHITA, KANSAS