

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Citation Oil & Gas Corp

Address: P.O. Bos 690688, Houston, TX 77269-0688

Phone: (281) 517-7194 Operator License #: 03553

Type of Well: Oil - TA'd Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 1/23/2004 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

LKC Depth to Top: 3880' Bottom: 4015' T.D. 4030'

API Number: 15 - 065-03227-00-00

Lease Name: Elrick Unit

Well Number: 12-1

Spot Location (QQQQ): - SW - SW - NE 2970 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 10 Twp. 10 S. R. 25 East West

County: Graham

Date Well Completed: 11/2/1957

Plugging Commenced: 4/26/2004

Plugging Completed: 4/26/2004

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten entries for LKC formation.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

In 1986, CIBP was set @3700' capped with cement to 3520' to TA well. On 4/26/2004, MIRU and tagged TOC @3520'. M&P'd 30 bbls gelled FW 3520' - 2300' & displ'd with 9 BLW; perf'd 2300' - 2301' 2 spf and M&P'd 100 sx 60/40 Poz with 10% gel; perf'd 1300' - 1301' 2 spf and M&P'd 115 sx 60/40 Poz w/10% gel. RU to 5-1/2" csg and pumped 20 sx 60/40 Poz; tied into 8-5/8" x 5-1/2" annulus and pumped 15 sx 60/40 Poz. KCC rep Jay Pfeifer on location for plugging. RDMO.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: N/A 99996

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Citation Oil & Gas Corp.

State of Texas County, Harris, ss.


Debra Harris (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Debra Harris

(Address) P.O. Box 690688

SUBSCRIBED and SWORN TO before me this 29th day of April, 2004

Notary Public: Renee Harrell My Commission Expires: 3-2-07



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED MAY 03 2004 KCC WICHITA

Handwritten signature/initials at bottom right.