

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-033-21,099 -00-00

LEASE NAME Basnett

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER 1

2295 585 Ft. from N S Section Line

340 1290 Ft. from W W Section Line

RECEIVED
MAY 24 2004
KCC WICHITA

LEASE OPERATOR American Warrior, Inc.

SEC. 10 TWP. 34S RGE. 18 (E) or (W)

ADDRESS P.O. Box 399, Garden City, KS 67846

COUNTY Comance

PHONE # 620-275-2963 OPERATOR'S LICENSE NO. 4058

Date Well Completed 7/17/2000

Character of Well Good

Plugging Commenced 4/1/2004

(Oil, Gas D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/6/2004

The plugging proposal was approved on 4/1/2004 (date)

by Scott Alberg (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 5266 Bottom 5314 T. D. 6020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>				<u>8 5/8</u>	<u>633</u>	<u>None</u>
<u>Prod</u>				<u>4 1/2</u>	<u>6020</u>	<u>4100</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Lay down rods and tubing, set CIBP at 5197', dump 2 sacks portland cement with dump bailer, stretch and cut 4 1/2 at 4100'

Lay down 4 1/2 - 4/6/2004 - run 1100' of 2 3/8 tubing, Allied spot 15 gel, 50 cement at 640', 50 cement at 320', 40 cement

At 40', 10 cement, 60/40, 6% gel, topped 1 1/2 yard 2500 lb concrete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.


STATE OF Kansas COUNTY of Barber, ss.

John Swinford (Employee of Operator) or (Operator) of above described well, being

first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 21 day of May 2004

Glenda Morrison
Notary Public

My Commission Expires: November 30, 2006

Am