

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-077-20206-00-01

LEASE NAME NEWBERRY

WELL NUMBER 2

TYPE OR PRINT
NOTICE- Fill out completely
and return to Cons. Div.
office within 30 days.

4920 Ft. from S Section Line

500 Ft. from E Section Line

SEC. 35 TWP. 31 RGE. 9 ☐ E ☒ W

COUNTY Harper

Date Well Completed

Plugging Commenced 4/21/04

Plugging Completed 4/21/04

LEASE OPERATOR McCoy Petroleum Corp.

ADDRESS 8080 E Central, Suite 300, Wichita, Ks 67206

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/15/04 (date)

by Steve VanGiesen (KCC District Agent's Name),

Is ACO-I filed? yes If not, Is well log attached? yes

Producing Formation Depth to Top Bottom T.D. 4480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	218'	none
Production				5 1/2"	4427'	2009'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Quality Well Service, Inc. plugged well as follows: Pump 50 sacks, shut in 45 min, bleed off. Rip pipe at 2219', work pipe-no gain, rip 2009', work free. Pulled to 1300', pump 50 sacks cement. Pull to 700', pump 50 sacks cement. Pull to 270', circulate cement to surface with 100 sacks cement. Pull rest of pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, Ks 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick ss.

Scott Hampel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address) 8080 E Central, Ste. 300, Wichita KS 67206


RECEIVED

APR 30 2004

KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 29th day of April, 2004

My Commission Expires 11-4-07



Form CP-4
Revised 05-88