

STATE OF KANSAS
STATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,936-00-00

LEASE NAME Hissom

WELL NUMBER 1-3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

1850 Ft. from S Section Line

130' East of NWSU
SEC. 3 TWP. 34 RGE. 29W (E) or (W)

LEASE OPERATOR Vess Oil Corporation

COUNTY Meade

ADDRESS 8100 E. 22nd. St. N. Bldg. 300 Wichita, Ks. 67226

Date Well Completed 1-4-1994

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Plugging Commenced 5-4-04

Character of Well Oil

Plugging Completed 5-6-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 5030

5874

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf.</u>				<u>8-5/8"</u>	<u>1473'</u>	<u>None</u>
<u>Prod</u>				<u>4-1/2"</u>	<u>5831'</u>	<u>3022'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each set. Pumped bottom with 25 sacks 60/40 pos, 6% gel w/200# Hulls, released plug and displaced with 70 bbls. water. Cut pipe loose @3022', pulled up to 1480', pumped 10 sacks gel and 50 sacks cement, pulled up to 500', pumped 40 sacks cement, pulled up to 40' and topped off with 30 sacks cement. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.
(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED

MAY 13 2004

KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 11th day of May, 2004

[Signature]
Notary Public

My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form 05
Revised 05-