

RECEIVED

MAY 14 2004

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003 or Print on this Form Form must be Signed All blanks must be Filled

15-015-19499-00-00

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil
The plugging proposal was approved on: 5/4/04 - 4:00 p.m.
by: Bill Johnson
Is ACO-1 filed? Yes No
Producing Formation(s): Lansing, Kansas City

API Number: 15-015-95,336
Lease Name: Burlingame-Stokes A
Well Number: 38
Spot Location (QQQQ): SE - SE - SW
450' Feet from North / South Section Line
2935 Feet from East / West Section Line
Sec. 28 Twp. 25S S. R. 05E East West
County: Butler
Date Well Completed: 10/8/47
Plugging Commenced: 5/6/04
Plugging Completed: 5/11/04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Lansing and Kansas City.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Old CIBP @ 2100'. Tubing to 1985', United mix and spot 125 sx Class A, 3% cc w/100# hulls. Pull tubing. Wireline tag top of cmt at 1320'. Old sqz at 145'. Perf @ 275'. Pump in at cmt 200# - no circ. Perf at 100' - pump in @ 200# no circ. Pump into 10-3/4 - pressure to 500# with packer at 62'. Mix and pump 50 sx 60/40 pozmix, 4% gel. Pull out. Tbg to 62' Circ 21 sx more. Pull out top off @ 20 sx. 5/7/04 - Run tbg back to 280' and re-circ cement 50sx. Pull out-top off 5 sx.


Name of Plugging Contractor: United Cementing and Acid Company, Inc. License #: 30437
Address: 2560 W. 6th, El Dorado, KS 67042

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

W. R. Horigan (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 12th day of May
[Handwritten Signature] My Commission Expires:
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]



United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing
(316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
2510 West 6th Street • El Dorado, KS 67042

RECEIVED SERVICE TICKET

MAY 14 2004

✓ 5436

KCC WICHITA

DATE 5-6-04

COUNTY Butler CITY _____

CHARGE TO Vess

ADDRESS _____ CITY _____ ST _____ ZIP _____

LEASE & WELL NO. BURLINGAME/STOKES # 38 CONTRACTOR Simmons Well serv.

KIND OF JOB Old hole plug SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. Vess yard 10:30 OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
1255x	class A 3% cc @ 5.92		500.00
45x	calcium chloride @ 26.18		740.00
855x	60/40 po2 4% gel @ 4.90		106.60
35x	gel @ 9.70		420.75
			29.10
2175x	BULK CHARGE		212.10
	BULK TRK. MILES 10.85	min chg	94.50
7	PUMP TRK. MILES		
	PLUGS		
		SALES TAX	111.49
		TOTAL	2215.10

T.D. _____ CSG. SET AT _____ VOLUME _____

SIZE HOLE _____ TBG SET AT _____ VOLUME _____

MAX. PRESS. _____ SIZE PIPE _____

PLUG DEPTH _____ PKER DEPTH _____

PLUG USED _____ TIME FINISHED 1:30

REMARKS: Ran 2 3/8" Tubing down 7" to 1985ft. Brake circulation Mix & pump 125 5x class A 3% cc & pulled tubing out. Ran wire line & tagged cement at 1325ft. Shot holes in 7" at 275ft, & ran packer in at 220ft. Pump on & it did not circulate, Shot hole at 100ft, Ran packer in at 62ft. Brake circulation, Mix & pump 50 5x 60/40 po2 4% gel Tapped off with 35 5x

NAME <u>60/40 4% gel</u>	UNIT NO.	NAME	UNIT NO.
<u>Mitch Rupp P-15</u>		<u>Jerry Hudson B-1</u>	
<u>James K. Honan II #26</u>			
CEMENTER OR TREATER		OWNER'S REP.	



United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing
(316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
2510 West 6th Street • El Dorado, KS 67042

RECEIVED

MAY 14 2004

SERVICE TICKET

KCC WICHITA

5370

DATE 5-11-04

COUNTY Butler CITY _____

CHARGE TO Vess Oil Corp

ADDRESS _____ CITY _____ ST _____ ZIP _____

LEASE & WELL NO. BURLINGAME/STOKES #38 CONTRACTOR SEMMONS

KIND OF JOB Re Plug Old hole SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. Vess YARD 4:00^P OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
55 SX	60/40 poz		250.00
2 SX	BSL		
57 SX	BULK CHARGE		
MIX	BULK TRK. MILES		
N/A	PUMP TRK. MILES		
	PLUGS		
		SALES TAX	
		TOTAL	

T.D. CEMENT @ 2.10'
 SIZE HOLE _____
 MAX. PRESS. _____
 PLUG DEPTH _____
 PLUG USED _____

CSG. SET AT _____ VOLUME _____
 TBG SET AT _____ VOLUME _____
 SIZE PIPE 2 7/8 Tub
 PKER DEPTH _____
 TIME FINISHED 5:00^P

REMARKS: KAN TUBING @ TAG CEMENT @ 2.10' - MIX & Pump 50 SX 60/40 poz.
470BSL CIR. CEMENT TO SURFACE - Pull TUBING - Top well
off with 5 SX 60/40 poz 470BSL - WELL REMAINED FULL

EQUIPMENT USED

NAME Mitch Rupp UNIT NO. P-15
Neal Rupp #04
 CEMENTER OR TREATER

NAME _____ UNIT NO. _____

 OWNER'S REP.