


15-153-20099-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Rawlins County, Sec. 20 Twp. 1S Rge. (E) 34 (W)  
Location as "NE/CNW/SW" or footage from lines C SW/4 NE/4



Locate well correctly on above Section Plat

Lease Owner Skelly Oil Company  
Lease Name Frances H. Sabatka Well No. 3  
Office Address 1860 Lincoln Street - Denver, Colorado 80203  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 26, 1970  
Application for plugging filed November 26, 1970  
Application for plugging approved December 1, 1970  
Plugging commenced November 26, 1970  
Plugging completed November 26, 1970  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Box 157, Morland, Kansas 67650

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
DRY HOLE						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

11/26/70 - Ran drill pipe open ended and plugged well as follows:

100 sacks of cement at 2200', 40 sacks of cement at 390'; 10 sacks of cement at 40' to surface.

Job complete at 10:30 P.M. 11-26-70.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 24 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gabbert-Jones, Inc. 12-24-70  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF COLORADO, COUNTY OF DENVER, ss.  
A. H. Hurley (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. H. Hurley*  
1860 Lincoln Street - Denver, Colorado 80203  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1970

My commission expires November 4, 1973

*Geraldine Gate*  
Notary Public.

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

15-153-20099-00-00

FRANCIS H. SABATKA #3  
 C SW NE Section 20-1S-34W  
 Rawlins County, Kansas

Commenced: November 17, 1970  
 Completed: November 26, 1970

OPERATOR - Skelly Oil Company

DEPTH		FORMATION	REMARKS
From	To		
0	2274	Shale	Ran 9 joints 8-5/8" casing, set @ 370' w/250 sacks cement.
2274	2423	Shale and shells	
2423	2603	Lime and shale	
2603	2841	Sand and shale	
2841	3028	Lime and shale	
3028	3065	Stone Corral	
3065	3148	Shale and lime	
3148	3477	Lime and shale	
3477	3603	Lime	
3603	4370	Lime and shale	
4370	TD		Dry and abandoned.

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW NE Section 20-1S-34W, Rawlins County, Kansas, to the best of my knowledge and belief.

*James S. Sutton, II*  
 JAMES S. SUTTON, II

STATE OF KANSAS     )  
                               ) SS  
 COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 4th day of December, 1970, personally appeared James S. Sutton, II, wo me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Barbara J. Layton*  
 Barbara J. Layton, Notary Public

My Commission Expires Feb. 1, 1972.



RECEIVED  
 STATE REGENERATION COMMISSION  
 DEC 24 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 12-24-70