

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20565-00-00

LEASE NAME Micek B

WELL NUMBER #1

SPOT LOCATION SW SW SE

SEC. 20 TWP. 1S RGE. 34 ~~(W)~~ or (W)

COUNTY Rawlins

Date Well Completed Oct. 6, 1984

Plugging Commenced 11-2-84

Plugging Completed 11-2-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Fagin Exploration

ADDRESS P.O. Box 6, Liberal, KS 67901

PHONE # (316) 624-3767 OPERATORS LICENSE NO. 8301

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing/KC Depth to top 4161 bottom 4310 T.D. 4400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	Salt water	4306	4310			
" "	Salt water	4262	4268			
" "	Salt water	4214	4217			
" "	Salt water	4161	4167			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 3 sx cotton seed hulls ahead of cement
50 sx 50/50 poz, 6% gel, 3% CaCl₂ 4161-4100
20 sx gel in water 4100 to 2240'
250 sx 50/50 poz 6% gel, 3% CaCl₂ 2240' to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____
Address Box 47
Oberlin, KS 67749

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Seward, ss.

R.F. Burke

(employee of operator) of


(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R.F. Burke

(Address) P.O. Box 6, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 5 day of November, 19 84

My Commission expires:



A. J. Parnell
Notary Public