

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 153 15-154-20,743-00-00

LEASE NAME Weishapl

WELL NUMBER 1

4470 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 1S RGE. 34 ~~XXXX~~ (W)

COUNTY Rawlins

Date Well Completed 11-10-89

Plugging Commenced 11-10-89

Plugging Completed 11-10-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-10-89 (date)

by State Plugger, Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud in hole. 1st plug from 3000' to 2920' w/20 sx. 2nd plug from 2250' to 1850' w/100 sx. 3rd plug from 350' to 190' w/40 sx. 4th plug from 40' SB to surface w/10 sx. Rathole 15 sx. Mousehole-10 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

150 N. Main, Suite 801

(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 89

My Commission Expires: _____

Sharan J. Branstetter
Sharan J. Branstetter, Notary Public
May 18, 1993

