

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-153-
API NUMBER ~~155~~-20-582-00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Segne

WELL NUMBER 21-1

SPOT LOCATION 330FWL 1610FSL

SEC 21 TWP. 35 (X) or (W)

COUNTY Rawlins

Date Well Completed 12-3-84

Plugging Commenced 12-4-84

Plugging Completed 12-4-84

LEASE OPERATOR Greenwood Resources

ADDRESS 315 Inverness Way So., Englewood, CO

PHONE # (303) 790-1266 OPERATORS LICENSE NO. 8389

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita, (Marion Schmidt)

Is ACO-1 filed? no If not, is well log attached? yes

Producing formation none Depth to top ---- bottom -- T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Lansing/Kansas</u>	<u>water</u>	<u>4232</u>	<u>4280</u>			
				<u>8-5/8"</u>	<u>304'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. set 30 sack plug at 3120' with 50-50 Poz mix, 2% Gel, 3% CaCl, 100 sack plug at 2070', 2% Gel, 3% CaCl 1 sack Flo-Seal, 60 sack plug at 330' 50/50 Poz, 2% Gel, 3% CaCl 10 sack plug at 40' with solid B.P.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling License No. _____

Address Wichita KS

RECORDED
STATE CORPORATION COMMISSION

STATE OF KS COUNTY OF _____, ss.

James P. Ryder (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 315 Inverness Way So.

Englewood CO.

SUBSCRIBED AND SWORN TO before me this 11 day of December, 1984

Darlene S. Bradley
Notary Public

DARLENE S. BRADLEY
315 Inverness Way South
Englewood, CO 80112 Form CP-4 1-84
Revised 06-83



DEC 17 1984
12-17-84
CONS. DIV. WICHITA
WICHITA, KANSAS