

API NUMBER 15-153-20,793-00-00

LEASE NAME Skolout

WELL NUMBER #2

330' Ft. from (S) Section Line

990' Ft. from (E) Section Line

SEC. 23 TWP. 1S RGE. 35 (E) or (W) (W)

COUNTY Rawlins

Date Well Completed _____

Plugging Commenced 9-17-92

Plugging Completed 9-18-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 30684 *5373*

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-18-92 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation LKC Depth to Top _____ Bottom T.D. 4290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	301'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Fill w/heavy mud; set 1st plug @ 2985'-2885' w/25 sx; 2nd plug @ 2255'-1855' w/100 sx; 3rd plug @ 350'-190' w/40 sx; 4th plug @ 40'-surface w/10 sx w/wiper plug; mousehole 10 sx; rathole 15 sx; Total 200 sx 60-40 posmix 6% gel 1/4# Flocel.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 22nd. day of September, 1992

Angela Woodard
Notary Public

My Commission Expires: March 20, 1993

RECORDS-67202
STATE CORPORATION COMMISSION
SEP 24 1992
Wichita, Kansas