

15-153-30100-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
20 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER March 1, 1962

LEASE NAME Savage

~~15-153-20692-00-00 #6~~

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1980  
660 Ft. from S Section Line

1320/660 Ft. from E Section Line

SEC. 14 TWP. 1S RGE. 35W (E) or (W)

LEASE OPERATOR Burch Exploration Inc.

ADDRESS 6415 Nannette Way, Colorado Springs, Colorado 80907 COUNTY Rawlins

PHONE#( 303 ) 598-2515 OPERATORS LICENSE NO. 7448

Date Well Completed 3-8-62

Character of Well \_\_\_\_\_

Plugging Commenced 4-15-85

~~XXXXXX Gas, D&A, XXXX, XXXXXX Water Supply XXXX~~

Plugging Completed 4-17-85

do you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Yes

Producing Formation Lansing K.C. Depth to Top 4078 (-927) Bottom 4337 (-1186) 4370 (-1219)

show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shale		Surface	324	8 5/8	X	None
Lansing K.C.		Surface	4367	4 1/2	X	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Run 2 3/8 tubing with bit. Hole clean to 2750. Clean out sand to 2850. Call state plugger Earl Goodrow. Pump 50 sks. of gel and 6 sks. of hulls down casing. Mix 180 sks. of cement 6% gel and 3% C.C. Fill casing 100 pounds of pressure. Mix 20 sks. of cement 6% gel and 3% C.C. Pump down 8 5/8 anylis. Fill casing 100 pounds standing pressure. Job complete. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe's Well Service License No. 6779

Address P.O. Box 115, Oberlin, Kansas 67749


CITY OF Kansas Decatur COUNTY OF Decatur, ss.

Melvin I. Taylor (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, circumstances, and matters herein contained and the log of the above-described well as filed that same are true and correct, so help me God.

(Signature) Melvin I. Taylor

(Address) 405 East 14th, Route 1, McCook, NE



AND SWORN TO before me this 2nd day of May, 19 85

Rhonda Sorenson  
Notary Public

My Commission Expires: December 4, 1985