

15-153-20359-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rawlins SEC. 17 TWP. 1S RGE. 35W E/W
 Location as in quarters or footage from lines:

Locate Well
 correctly on above
 Section Platt.

C SW SE
 Lease Owner Murfin Drilling Company
 Lease Name Wilkinson B-1 Well No. _____
 Office Address 617 Union Center Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 10-22-82
 Plugging completed 11-10-82
 Reason for abandonment of well or producing formation _____
 _____ Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom T.D. 4425'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	314'	none
				4-1/2"	4421'	1617'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged off bottom with 4 sacks cement, sand to 4200' and 4 sacks cement. Shot casing @3016', 2513', 2324', 2109', 1816', 1729', pulled a total of 39 joints of 4-1/2" casing. Plugged well with 4 sacks gel, 2 sacks hulls, 100 sacks cement, 36 sacks gel, 8-5/8" plug and 60 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1982

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION
 NOV 29 1982
 Notary Public
 CONSERVATION DIVISION
 Wichita, Kansas
 11-29-82


WELL LOG

WELL FILE

15-153-20359-00-00

COMPANY Murfin Drilling Company
 FARM WILKINSON "B" NO. 1
 RIG. NO. 3
 TOTAL DEPTH 4425'
 COMM. 8-24-79 COMP. 9-3-79
 CONTRACTOR Murfin Drilling Company

SEC. 17 T. 1S R. 35W
 LOC C SW SE



CASING
 10 10
 15 8 -5/8" csg. set @ 314' (8 jts., 307.28') ELEVATION
 12 6 w/250 sx. of 60-40 posmix, 3% CaCl.
 13 5
 PRODUCTION
 4 1/2" csg. set @ 4424' w/150 sx. (50 sx. of Class A + 50 sx. of 50-50 posmix.
 10% salt, 3/4% CFR-2 + 50 sx. Posmix, w/45 gallons of Latex)

270' Sand
 315' Shale
 1935' Sand & Shale
 2465' Shale & Sand
 2680' Sand & Shale
 2830' Shale
 2985' Shale & Sand
 3360' Sand & Shale
 3540' Shale & Sand
 3680' Sand & Shale
 4425' Lime & Shale R T D

State of KANSAS
 County of SEDGWICK

I, Wm. S. Shropshire, Asst. Gen. Mgr. of the Murfin Drilling Company Company
 upon oath state that the above and foregoing is a true and correct copy of the log of the WILKINSON "B" #1 well.

Subscribed and sworn to before me this 19th day of September 1979
Wm. S. Shropshire, Asst. Gen. Mgr.

My Commission Expires: May 21, 1983
 DP28 Linda Lynch

Linda Lynch NOTARY PUBLIC

STATE COMMISSIONER
 15-153-20359-00-00
 5-27-82
 CONSERVATION DIVISION
 Wichita, Kansas