

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-20,700-00-00
 LEASE NAME Sis V

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
554 Ft. from S Section Line
3194 Ft. from E Section Line
 SEC. 1 TWP. 1 RGE. 35XXXXX (W)
 COUNTY Rawlins

LEASE OPERATOR Abercrombie Drilling, Inc.
 ADDRESS 801 Union Center Wichita, KS 67202
 PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5422

Date Well Completed 12-22-87
 Plugging Commenced 12-22-87
 Plugging Completed 12-22-87

Character of Well D & A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist #6 Hays, KS Dale Balthazor State Pluggger

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size 5/8	Put in 3/26	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.


Pump mud to 3010. 1st plug from 3010 to 2910 w/25sx. Pump mud to 2200', 2nd plug from 2200 to 1800' with 100sx; Pump mud to 350'. 3rd plug from 350' to 200' with 40sx. Pump mud to 40', set solid bridge & cement from 40' to surface with 1-sx. Pump 10 sx in mousehole & 15sx in rat-hole. All cement 60/40 posmix 6% gel.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, inc. License No. 5422
 Address 801 Union Center Wichita, KS 67202
 STATE OF Kansas COUNTY OF Sedgwick, ss. 01 05 1988

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
 (Address) 801 Union Center
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of January, 1988



Janet A. Stuck
 Notary Public

My Commission Expires: 12-29-90