

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-30096-00-00

LEASE NAME Chadderdon

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

3300
~~660~~ Ft. from S Section Line

4630
~~1320~~ Ft. from E Section Line

SEC. 13 TWP. 1-S RGE. 35W (#) or (W)

LEASE OPERATOR Burch Exploration Inc.

ADDRESS 6415 Nannette Way, Colorado Springs, Colorado 80907

PHONE# (303) 598-2515 OPERATORS LICENSE NO. 7448

COUNTY Rawlins

Date Well Completed 4-3-1963

Character of Well _____

Plugging Commenced 4-19-85

(~~Oil, Gas, D&A, SWD, Input, Water Supply Well~~)

Plugging Completed 4-23-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Lansing K.C. Depth to Top 4054-925 Bottom 4318 T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shale		Surface	288	8 5/8	X	None
Lansing K.C.		Surface	4499	5 1/2	X	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Run 2 3/8 tubing to 3150. Had Halliburton spot 15 sks. of sand over perfs. Mix and spot 10 sks. of cement on top of sand. Pull tubing. Hook up to 5 1/2 casing. Mix 3 sks. of hulls and 15 sks. of gel. Pump down casing. Mix 170 sks. of cement 6% gel and 3% C.C. Pump down casing. Pump 20 sks. of cement 6% gel and 3% C.C. down 8 5/8 anylis. Check job 4-23-85.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe's Well Service License # 8779

Address P.O. Box 115, Oberlin, Kansas 67749

STATE OF Kansas COUNTY OF Decatur, ss.

Melvin L. Taylor

(Employee of Operator) of (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Melvin L. Taylor

(Address) 405 East 14th, Route 1, McCook, NE 69001



SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 85

Rhonda Salem
 Notary Public

My Commission Expires: December 4, 1985

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 06 1985
 05-06-1985
 CONSERVATION DIVISION
 Wichita, Kansas

Cement in 5½ down to 400' on wire line. Call Halliburton for 100 sks. of cement.
Mix 100 sks of 50/ 50 poz mix. 6% gel and 3% C.C. Fill casing 100 pounds pressure.
Check casing 4-24-85. Casing still full. Dig out 5' below ground level. Cut off 5½
and 8 5/8 casing. Weld cap over casing and cover up. Job complete.

