

15-153-19008-00-00


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rawlins County. Sec. 12 Twp. 1S Rge. (E) 35 (W)

Location as "NE/CNW%SW%" or footage from lines C SW SE
Lease Owner Burch Exploration, Ltd.
Lease Name SIS Well No. 1
Office Address 1011 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed October 23, 19 63
Application for plugging filed verbally - October 22, 19 63
Application for plugging approved verbally - October 22, 19 63
Plugging commenced October 23, 19 63
Plugging completed October 23, 19 63
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4290 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole with heavy mud to 600'
Set 1st plug at 600' w/20 sx cement.
Filled hole with heavy mud to 280'
Set 2nd plug at 280' w/20 sx cement.
Set 3rd plug to surface at 40' w/10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1963
10-29-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. contractor
B. Lynn Herrington (employee of ~~owner~~ or ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington
801 Union Center, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 63

Deak Lays Negke

My commission expires June 16, 1967

Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Burch Exploration, Ltd.
CONTRACTOR: Abercrombie Drilling, Inc.
FARM: SIS #1
LOCATION: C SW SE Section 12-1S-35W
Rawlins County, Kansas
COMMENCED: October 13, 1963
COMPLETED: October 23, 1963

0	960	Shale
960	1550	Shale & Shells
1550	1770	Sand
1770	2048	Shale & Sand
2048	2200	Shale
2200	2312	Hard Sand
2312	2430	Shale
2430	3957	Lime & Shale
3957	4290	Lime
	4290	Rotary Total Depth

ELEVATION: 3082' K. B.

ELECTRIC LOG TOPS:

Topeka	3793'	(- 711)
Deer Creek	3834'	(- 752)
Oread	3876'	(- 794)
Douglas	3964'	(- 882)
Lansing	4008'	(- 926)
Base Kansas City	4277'	(-1195)
Total Depth	4290'	(-1208)


RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1963
CONSERVATION DIVISION
Wichita, Kansas

Set 8-5/8" surface casing at 279' with 225 Sx Cement

DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the SIS #1, C SW SE, Section 12-1-35W Rawlins County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.


B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 25th day of October, 1963.


Leah Faye Hefke

My commission expires June 16, 1967.