

RECEIVED

MAY 20 2004

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-23,067-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C. KCC LICENSE # 5056

ADDRESS 9431 E. Central, Suite 100 (owner/company name) CITY Wichita (operator's)

STATE KS. ZIP CODE 67206-2543 CONTACT PHONE # (316) 684-8481

LEASE FAIR "A" WELL# 1-10 SEC. 10 T. 21S R. 11 (East/West)

110'N. C - N/2 - NW - NE SPOT LOCATION/QQQQ COUNTY Stafford

440 FEET (in exact footage) FROM S(N) (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 228' CEMENTED WITH 240 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 2556' CEMENTED WITH 50 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2286'-2288, 2363'-2364.5, 2376.5-2378'. BP @ 2527

*KCC  
all  
5/27/04  
ref 109*

ELEVATION 1980' 1780' T.D. 2660' PBDT 2527' ANHYDRITE DEPTH 498'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (620) 793-0915 / (620) 786-5783 (Cell)

ADDRESS P.O. BOX 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925

ADDRESS 401 West Main, Lyson, KS. 67554 (company name) PHONE # (620) 727-3410 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 05/17/2004 AUTHORIZED OPERATOR/AGENT: Loveness Mpanje  
(signature)

*6/04*

*8/04*

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

## SAMPLE LOG

Fair 'A' 1-10

LOCATION: 100' South of C N/2 Nw Ne  
API: 15-185-230670000

Section 10 T 21s R 11w  
Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.  
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 21-Nov-97  
COMPLETED: 26-Nov-97

TOTAL DEPTH: DRILLER 2660 FEET  
LOGGER 2658 FEET

Ground Elevation: 1780  
KB Elevation: 1789

### LOG

0 -	200 FEET	Top Soil and Sand
200 -	512 FEET	Shale
512 -	530 FEET	Anhydrite
530 -	2660 FEET	Limestone, Shale and Dolomite

### CASING RECORDS

Spud @ 10:30 am on 11-21-97. Drilled 12-1/4" hole to 230'. Ran 5 joints of new 20# 8-5/8" surface casing 216.16' set at 228' KB. Cemented with 240 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 2:00 pm on 11-21-97 by HOWCO. Good returns. Ticket # 308185.

Ran 64 jts used 4-1/2" casing. Tallied 2547.03', set at 2556.03' KB. Cemented with 25 sacks lite and 25 sacks FG Holl mix. Plug down at 7:15 am on 11-16-97 by HOWCO. Ticket # 308206. Centralizers on jts 1-3-8-10. Scratchers from 2260'-2310' and 2350'-2400'. Plug rathole with 15 sacks and plug mousehole with 10 sacks.

RECEIVED  
MAY 20 2004  
KCC WICHITA

### DEVIATION SURVEYS

1/4 degree(s) at 230 feet  
1-1/4 degree(s) at 1630 feet

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.  
9431 E Central, Suite 100  
Wichita, KS 67206

May 24, 2004

Re: FAIR A #1-10  
API 15-185-23067-00-00  
N2NWNE 10-21S-11W, 440 FNL 1980 FEL  
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888