

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-153-20,743-000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Weishapl WELL NO. 1 WELL LOCATION 150' S of NW NE COUNTY Rawlins

SEC. 19 TWP. 1S RGE. 34 (~~EX~~) (W) TOTAL DEPTH 4350' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 310' CEMENTED WITH 200 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 3000'-20 sx. 2nd plug at 2250'-100 sx. 3rd plug at 350'-40 sx. 4th plug at 40' SB-10 sx. Rathole-15 sx.

Mousehole-10 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 8:30 a.m. on 11-10-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

William Craig, Sr. PHONE # (913) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Johnston
(Operator or Agent)

DATE: 12-04-89

RECEIVED
STATE CORPORATION COMMISSION
DEC - 5 1989
12-5-89
CONSERVATION DIVISION
Wichita, Kansas