

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-153-30108-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1966

8-22-66

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company.

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Betty Skolout Well No. 1

Location CNE-SW Sec. 36 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4175

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:30PM Day 17 Month 8 Year 66

The Above well was plugged as follows:

239'--8 5/8" Surface pipe, cement circulated with 115 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 240', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 8/22/66
INV. NO. 3795-W