

KANSAS

Form CP-3
Rev. 6-4-68

2

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20082-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas
8-10-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Spicka Well No. 1

Location CE/2-SE-NW Sec. 35 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:30 AM Day 5 Month 8 Year 1970

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 2050'.

Circulated hole with heavy mud. Pulled DP to 2290' and displaced 100 Sx. cement thru
DP from 2290' to 1965'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/10/70
INV. NO. 2356-4

Signed: M. L. Nichols
Well Plugging Supervisor