

KANSAS

*28*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20022-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
7-12-68

Operator's Full Name T. L. Ferrier,

Complete Address: 300 Schweiter Building, Wichita, Kansas. 67202

Lease Name Mary Sabatka Well No. 1

Location CSW-SE Sec. 33 Twp. 1 Rge. (E) (W) 35

County Rawlins Total Depth 4435

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kans. License No. \_\_\_\_\_

Operation Completed: Hour 10:00 AM Day 9 Month 7 Year 1968

The Above well was plugged as follows:

314'--8 5/8" Surface pipe, cement circulated with 275 Sx.  
Top of Dakota section @ 1475'.

Circulated hole with heavy mud. Pulled DP to 1700' and displaced 100 Sx. cement thru  
DP from 1700' to 1375'. Pulled DP to 340' and displaced 20 Sx. cement thru DP from  
340' to 280'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols  
Well Plugging Supervisor

DATE 7/12/68

INV. NO. 8094-W