

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20090-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-9-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Husky Oil Company of Delaware,

Complete Address Box #380, Cody, Wyoming. 82414

Lease Name Husky-Reeh Well No. 3-31

Location CNE-NW Sec. 31 Twp. 1 Rge. (E) (W)35

County Rawlins Total Depth 4530'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kans. License No. \_\_\_\_\_

Operation Completed: Hour 3:00 PM Day 3 Month 11 Year 1970

The above well was plugged as follows:

324'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota Section @ 2125'.

Circulated hole with heavy mud. Pulled DP to 2350' and displaced 100 Sx. cement thru  
DP from 2350' to 2025'. Pulled DP to 330' and displaced 20 Sx. cement thru DP from  
330' to 270'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Decker*  
Well Plugging Supervisor

INVOICED

DATE 11/9/70  
INV. NO. 2827-W