

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21888-00-01
Spot: NENESWSE Sec/Twnshp/Rge: 13-15S-12W
1275 feet from S Section Line, 1355 feet from E Section Line
Lease Name: HEINZE A Well #: 5
County: RUSSELL Total Vertical Depth: 3420 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

PROD Size: 4.5 feet: 3349 200 SX CMT
SURF Size: 0 feet: 0
SURF Size: 8.625 feet: 209 150 SX CMT

\$111¹⁵

Well Type: SWD UIC Docket No: D21478.0 Date/Time to Plug: 04/05/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PAUL NIXON Company: NIXON, R.P. OPERATIONS, INC. Phone: (785) 623-1059

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2004 10:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Packer stuck in the hole at 2400'.
Well squeezed at 760' w/270 sxs.
Cement in head.
Tied onto casing and pumped 200 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Max. P.S.I. 800#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3350	3420		

RECEIVED
APR 29 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*
(TECHNICIAN)

INVOICED
DATE 4-29-04
INV. NO. 200.4061475

APR 26 2004

replacement card

R & H OIL & GAS CO
RUSSELL KS

13-15S-12W
40'E. C SW-4
SE/4

5 HEINZE A

site: 7 N & 3-1/4 E OF BEAVER KS	city: RUSSELL	API 15-167-21038
contr: BERGMAN DRILLING,	field: DRISCOLL	
geol:		
lr date 03/05/82	spd date 03/15/82	drilg comp 03/21/82
		card issued 02/03/83
		last revised 01/20/97

ELV: NA
 tcps.....depth/datum
 RTD.....3300
 DTD.....3420
 NO TOPS RPTD

IP status:
 SWDW, GRAN 3350-3420, 09/19/83
 CORR & INFO REL: 1/20/97 - CORR DTD (WAS 3405);
 WAS TEMP COMP
 CSG: 8-5/8" 209.55, 4-1/2" 3349
 NO CORES OR DSTS
 MICT - CO TO 3300, DD 3420 TD, (GRAN, WSH OH),
 COMP AS SWDW - INJECTION RATE SATISFACTORY.
 9/19/83 - NO OTHER INFO AVAILABLE

COPYRIGHT 1997
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS