

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22680-00-00
Spot: S2SENWSE Sec/Twnshp/Rge: 29-11S-18W
1485 feet from S Section Line, 1650 feet from E Section Line
Lease Name: JOHNSON E Well #: 6
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3747 w/250 sxs cmt
SURF Size: 8.625 feet: 241 w/200 sxs cmt

88
121

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2004 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs gel.
7 joints tubing stuck in the hole.
Top of fish at 3250'.
DV at 1267' set with 360 sxs.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2004 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3220'.
Tied onto and pumped 10 sxs gel followed with 50 sxs cement with 300# hulls.
Pulled up to 1920' and spotted 75 sxs cement with 200# hulls.
Pulled up to 1300' and circulated cement up 5 1/2" x 8 5/8" with 80 sxs cement.
POOH. Swaged onto 5 1/2" and pumped 20 sxs cement.
Max. P.S.I. 1000#. S.I.P. 1000#.

Perfs:

RECEIVED
MAY 26 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 5-26-04
TV. NO. 20040616-04

MAY 25 2004

CHAMPLIN PETROLEUM CO
 6441 NW GRAND BLVD #300 #6 JOHNSON "E" C S/2 SE NW SE. 29-11-18W
 OKLAHOMA CITY, OK 73116
 CONTR RED TIGER DRG CO CTY ELLIS

GEOL _____ FIELD RIVERVIEW

E 1957 KB CM 10/17/81^{FARD} ISSUED 12/10/81 IP P 15 BO & 753 BWPD,

API 15-051-22,680

ARB 3518-3522

+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
TOP		2937	- 980
TOR		3183	-1226
LANS		3206	-1249
B KC		3435	-1478
ARB		3488	-1531
RTD		3750	-1793
Avh		1274	+683

8 5/8" 241; 5 1/2" 3747

NO DST'S

MICT - CO, PF (L ARB), 10/3549-3554, SWB
 16 BW, RBSO, SET BP @ 3528 PF (L ARB)
 3/3518-3522, SWB DRY/1 HR, AC 500 G,
 SWB 6 HRS REC 166BF, 5% O, R&T, POP,
 P 15 BOPD & 753 BWPD, 12/4/81

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

11310701